BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT45685

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/10/2020-21, Date: 24-11-2020

Name of Work:Drilling of Borewell Providing and Installing Pump Motor and other accessories and Development of Parks and Providing Children Play and Gym Equipments at NTI Layout, Gurudharshan Layout in ward no 09 (Vidyaranyapura)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K B ALANKAR ( )	
				In Figures	In Words
1	2	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its quality & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Each BW	3955.27	Rupees Three Thousand Nine Hundred Fifty Five and Twenty Seven Paise Only
2	100	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars and cap etc.,) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 0 to 50 m	Rmtr	364.25	Rupees Three Hundred Sixty Four and Twenty Five Paise Only
3	100	50 to 100 m	Rmtr	463.97	Rupees Four Hundred Sixty Three and Ninety Seven Paise Only
4	100	100 to 150 m	Rmtr	478.66	Rupees Four Hundred Seventy Eight and Sixty Six Paise Only
5	100	150 to 200 m	Rmtr	562.64	Rupees Five Hundred Sixty Two and Sixty Four Paise Only
6	100	200 to 250 m	Rmtr	665.51	Rupees Six Hundred Sixty Five and Fifty One Paise Only
7	100	250 to 300 m	Rmtr	734.79	Rupees Seven Hundred Thirty Four and Seventy Nine Paise Only
8	100	300 to 350 m	Rmtr	866.0	Rupees Eight Hundred Sixty Six Only
9	160	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty	Rmtr	1448.59	Rupees One Thousand Four Hundred Forty Eight and Fifty Nine Paise Only
10	36	Providing 250mm dia PVC Pipe 6kg/cm etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	1154.67	Rupees One Thousand One Hundred Fifty Four and Sixty Seven Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K B ALANKAR	
				In Figures	In Words
11	2	Providing and fixing Borewell Cap & Clamp Set etc., complete and as per the directions of the Engineer-in-charge of the work	Set	1889.46	Rupees One Thousand Eight Hundred Eighty Nine and Forty Six Paise Only
12	2	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps etc., complete and as per the directions of the Engineer-in-charge of the work	No	66653.85	Rupees Sixty Six Thousand Six Hundred Fifty Three and Eighty Five Paise Only
13	640	GI Pipe 50 mm'B' class etc., complete and as per the directions of the Engineer-in-charge of the work	m	435.63	Rupees Four Hundred Thirty Five and Sixty Three Paise Only
14	108	Heavy Duty Collar 50 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	188.95	Rupees One Hundred Eighty Eight and Ninety Five Paise Only
15	2	Providing non-return valve 50 mm etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1889.46	Rupees One Thousand Eight Hundred Eighty Nine and Forty Six Paise Only
16	10	Providing Gate Valve 50 mm etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1889.46	Rupees One Thousand Eight Hundred Eighty Nine and Forty Six Paise Only
17	2	Supplying and Fixing Out Door Panel up to 15 HP etc., complete and as per the directions of the Engineer-in-charge of the work	No.	16270.35	Rupees Sixteen Thousand Two Hundred Seventy and Thirty Five Paise Only
18	1320	Submersible Cable 1x3x6.0 Sq.mm etc., complete and as per the directions of the Engineer-in-charge of the work	M	151.16	Rupees One Hundred Fifty One and Sixteen Paise Only
19	108	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00) etc., complete and as per the directions of the Engineer-in-charge of the work	L	92.37	Rupees Ninety Two and Thirty Seven Paise Only
20	2	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., complete and as per the directions of the Engineer-in-charge of the work	Each	306.51	Rupees Three Hundred Six and Fifty One Paise Only
21	70	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A 4 core 16 Sqmm etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	157.46	Rupees One Hundred Fifty Seven and Forty Six Paise Only
22	70	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	12.47	Rupees Twelve and Forty Seven Paise Only
23	60	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	79.78	Rupees Seventy Nine and Seventy Eight Paise Only
24	8	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	351.65	Rupees Three Hundred Fifty One and Sixty Five Paise Only

Signature of the contractor

Executive Engineer

Sl No.	Approved Qty.	Description	Unit	Approved Tender Rates of K B ALANKAR ( )	
				In Figures	In Words
25	2	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	283.42	Rupees Two Hundred Eighty Three and Forty Two Paise Only
26	2	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	No	3148.79	Rupees Three Thousand One Hundred Forty Eight and Seventy Nine Paise Only
27	12	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	182.65	Rupees One Hundred Eighty Two and Sixty Five Paise Only
28	2	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 5-32Amps Group A TPN etc., complete and as per the directions of the Engineer-in-charge of the work	No	1800.24	Rupees One Thousand Eight Hundred and Twenty Four Paise Only
29	46800	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.Cm	0.37	and Thirty Seven Paise Only
30	72	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strata by Manual Means etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	275.02	Rupees Two Hundred Seventy Five and Two Paise Only
31	200	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	217.29	Rupees Two Hundred Seventeen and Twenty Nine Paise Only
32	24	Filling the foundations KSRRB 2100-6. Filling the foundations trenches using approved sand as per drawing and technical specifications in 250mm layers, wherever necessary watering and ramming, including cost of all materials, labour complete as per specifications.	cum	3381.44	Rupees Three Thousand Three Hundred Eighty One and Forty Four Paise Only
33	48	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including watering, consolidation in layers of 15 cm thick including disposing of the sunplus earth with a lead of 200 mtrs etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	108.12	Rupees One Hundred Eight and Twelve Paise Only
34	64.35	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	Cum	369.64	Rupees Three Hundred Sixty Nine and Sixty Four Paise Only
35	7.56	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5676.9	Rupees Five Thousand Six Hundred Seventy Six and Ninety Paise Only
36	22.68	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	5113.89	Rupees Five Thousand One Hundred Thirteen and Eighty Nine
37	17.01	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	6100.84	Rupees Six Thousand One Hundred and Eighty Four Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K B ALANKAR ( )	
				In Figures	In Words
38	37.8	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. – do – cement mortar 1:3	sqm	105.7	Rupees One Hundred Five and Seventy Paise Only
39	81	Filling the foundations trenches using approved sand as per drawing and technical specifications in 250mm layers, wherever necessary watering and ramming, including cost of all materials, labour complete as per specifications.	cum	3381.44	Rupees Three Thousand Three Hundred Eighty One and Forty Four Paise Only
40	21.78	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	6100.84	Rupees Six Thousand One Hundred and Eighty Four Paise Only
41	180	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications. - using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 1200 mm	Sqm	3047.64	Rupees Three Thousand Forty Seven and Sixty Four Paise Only
42	850	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	1171.65	Rupees One Thousand One Hundred Seventy One and Sixty Five Paise Only
43	1200	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc complete as per specifications and directions of engineer in charge of the work	No	462.54	Rupees Four Hundred Sixty Two and Fifty Four Paise Only
44	486	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	41.95	Rupees Forty One and Ninety Five Paise Only
45	486	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	96.36	Rupees Ninety Six and Thirty Six Paise Only
46	2	Supply and fixing of pull down challenger: Metal All tubular steel of 2.50 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as neccessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixing. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a 5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2750x805x2685mm weight :85.4 kg safety Area:6287x4858 mm capacity_2 persons.	Nos	251298.18	Rupees Two Hundred Fifty One Thousand Two Hundred Ninety Eight and Eighteen Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K B ALANKAR ( )	
				In Figures	In Words
47	2	Supply and fixing of Seated Chest Press Metal All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a 5% NaCl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1955x733x2058mm weight :86.6 kg safety Area:5545x4470 mm capacity_2 persons.	Each	240827.42	Rupees Two Hundred Forty Thousand Eight Hundred Twenty Seven and Forty Two Paise Only
48	2	Supply and fixing of Self Weighted Rower All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1390x805x1100mm weight :42.4 kg safety Area:3790x3205 mm capacity_1person.	Each	172767.5	Rupees One Hundred Seventy Two Thousand Seven Hundred Sixty Seven and Fifty Paise Only
49	2	Supply and fixing of Elliptical cross Trainer metalAll tubular steel of 2.5 mm thickness are galavnized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1267x582x1764mm weight :43.5 kg safety Area:4322x3632 mm capacity_1 person.	Nos	146590.61	Rupees One Hundred Forty Six Thousand Five Hundred Ninety and Sixty One Paise Only
50	2	Supply and fixing of Rider metal All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 910x655x1270mm weight 29.5 kg safety Area:3310x3000 mm capacity_1 persons.	Nos	94236.82	Rupees Ninety Four Thousand Two Hundred Thirty Six and Eighty Two Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K B ALANKAR ( )	
				In Figures	In Words
51	2	Supply and fixing of Bicycle Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1000x498x1290mm weight :51.5 kg safety Area:3400x3498 mm capacity_1 persons.	Each	130884.47	Rupees One Hundred Thirty Thousand Eight Hundred Eighty Four and Forty Seven Paise Only
52	2	Supply and fixing of Twist Stepper All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1395x650x1750mm weight :39 safety Area 3795x3050 mm capacity_2 persons.	Each	188473.64	Rupees One Hundred Eighty Eight Thousand Four Hundred Seventy Three and Sixty Four Paise Only
53	2	Supply and fixing of Big shoulder wheel All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 845x810x1710mm weight :34 kg safety Area 3224x3376 mm capacity_2 persons .	Each	125649.09	Rupees One Hundred Twenty Five Thousand Six Hundred Forty Nine and Nine Paise Only
54	2	Supply and fixing HD Health Walker All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1065x615x1364mm weight :51 kg safety Area 4090x3555 mm capacity_1 person .	Each	146590.61	Rupees One Hundred Forty Six Thousand Five Hundred Ninety and Sixty One Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K B ALANKAR ( )	
				In Figures	In Words
55	2	Supply and fixing HD Squat Pushing Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2270x635x1640mm weight :60.2 kg safety Area 5300x3685 mm capacity_2 persons .	Each	225121.29	Rupees Two Hundred Twenty Five Thousand One Hundred Twenty One and Twenty Nine Paise Only
56	2	Supply and fixing Mini Ski. Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixning. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 1214x900x1347mm weight :45 kg safety Area 4214x3900 mm capacity_2 persons .	Each	167532.12	Rupees One Hundred Sixty Seven Thousand Five Hundred Thirty Two and Twelve Paise Only
57	2	Supply and fixing of HD Double Health Walker Metal: All tubular steel of 2.5 mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edgesand burrs. Zinc primer paint is applied at all the welding points prior to fixing. All metal parts are powder coated using AKZO nobel Great wall powder to the thickness of 80-120 microns. All metals parts are tested in our salt spray machine that uses a5% Na Cl Solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber : High quality grip rubber : 1 completely pre assembled equipment modules. Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly disply the GS mark as has been issued in the EN16630 saftey certificates. Size (1xWxH): 2015x615x1360mm weight :93 kg safety Area 5015x3015 mm capacity_2 persons .	Each	251298.18	Rupees Two Hundred Fifty One Thousand Two Hundred Ninety Eight and Eighteen Paise Only
58	2	Supply and fixing of HD Waist Twister Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped joints are robotic welded all welded joints are scalloped as necessary and welded to an approved MIG process All welds are dressed off removing all sharp edges and burrs Zonc primer paint is applied at all the welding points prior to finishing all metal parts are powder coated using AKZO Nobel Grate wall powder to the thickness of 80-120 microns all metal parts are tested in our salt spray machine that uses a 5% NACI solution in accordance to ISO7227 to speed up corrosion for 3000 hrs Rubber: High quality grip rubber is used for the handles Bearings: Maintenance free ball berings Scope of delivery 1 Completely pre assembled equipment modules Maintenance: Maintenance: Maintain accoring to EN 16630 EN16630 safety standard with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV CPSC or SGS only. The GS Marks EN16630 certificates must be in the name of tendering pat and not 3rd party. All products must clearly diply the GS mark as has been issued in the EN16630 saftey certificates. Size (LxWxH): 1460 x 1310 x 1150 mm weight : 39.1 kg safety Area 4360 x 4510 mm capacity_3 persons .	Each	136461.0	Rupees One Hundred Thirty Six Thousand Four Hundred Sixty One Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K B ALANKAR)	
				In Figures	In Words
59	5	Supplying of Granite benches as per approved drawing including cost of steel, materials, labour, transportation etc complete as per specification (Approved Rate)	Nos	11021.85	Rupees Eleven Thousand Twenty One and Eighty Five Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

20/02